

SPECIAL NOTE:- FOR APPROVAL OF ALT-I, ONLY THE SIGNATURES OF CONCERN JAG/SG & SAG OFFICERS OF ORIGINATING DEPT IS REQUIRED AS PER RLY BOARDS PROCEDURE ORDER NO. 2017/CE-I/CT/13/Procedure Simplication dt 21-04-2022.

TABLE OF INFRINGEMENT

RELEVANT STRUCTURE	DETAILS OF DIMENSION INFRINGING	ITEM NO. OF SOD	PRESCRIBED VALUE	PROPOSED VALUE	AMOUNT OF INFRINGEMENT
NIL	NIL	NIL	NIL	NIL	NIL

* THE TABLE OF INFRINGEMENT IS APPLICABLE FOR DETAILS AVAILABLE IN ESP ONLY.

DETAILS OF PROPOSED P-WAY

ITEMS	DETAILS
RAILS	60 Kg. (90 UTS)
TURNOUTS	1 IN 12 (CURVED SWITCH)
SLEEPER	PSC 1660 PKM
BALLAST	50mm SIZE 300mm CUSHION

FOR CONSTRUCTION OF TOWER WAGON SDG. AND SALOON SDG. IN C/W.

RAILWAY ELECTRIFICATION:- PINK BOOK ITEM NO.-46. UNDER PLAN HEAD-35 IN THE YEAR 2017-18.

SCOPE OF WORK:-

OPENING OF DOUBLE LINE TOWARDS MALDA END.

REFERENCES:-

DRAWING HAS BEEN PREPARED AS PER CE's DRG. No. Y-389-2016 (ALT-1) & SITE SURVEY & CE's DRG. NO. Y-390-2016 & CE's DRG. NO. Y-66-2020.

EXISTING WORKS SHOWN IN BLACK

PROPOSED WORKS SHOWN IN RED

WORKS TO BE DISMANTLED IN BLACK DOTTED

WORKS SHOWN IN GREEN TO BE DONE BY OPEN LINE.

NOTE:-

1. PASSENGER AMENITIES WILL BE PROVIDED AS PER LATEST RAILWAY BOARD GUIDE LINE.
2. S&T CABLE LAYING BESIDE LINE NO. 4 ASSISTED BY ENGG. SUPERVISOR.
3. P.I. BLDG. TO BE EXTENDED [RELAY ROOM, IPS ROOM & BATTERY ROOM]
4. SEPARATE DRAWING FOR DRAINAGE WILL BE PREPARED AND GOT APPROVED.
5. THERE ARE INFRINGEMENTS OF THE STRUCTURES OF SIGNALLING POSTS FIXED BETWEEN THE TRACKS, FOR WHICH CONDONATION WILL BE OBTAINED SEPERATELY.
6. ALL CHAINAGE HAS BEEN SHOWN FROM C.L. OF NEW STN. BLDG.

C.L. OF JANGIPUR ROAD STN. BLDG. (NEW) (JRLE)
Km 212.518 (FROM BDC)
CH. 0.00m, जंगीपुर रोड स्टेशन

DESIGNATION	NAME & SIGNATURE
C.P.D.E. EASTERN RAILWAY/KOLKATA	(RAJIV GUPTA)
C.T.P.M EASTERN RAILWAY/KOLKATA	(S. BISWAS)
CHIEF SIGN & TELE-COM ENGR./CON/II EASTERN RAILWAY/KOLKATA	( )
CHIEF ELECTRICAL ENGINEER/CON EASTERN RAILWAY/KOLKATA	( )
CHIEF ENGINEER/CON/II EASTERN RAILWAY/KOLKATA	(ANIL KUMAR)

DESIGNATION	NAME & SIGNATURE		
DIVISIONAL RAILWAY MANAGER EASTERN RAILWAY/MALDA	(YATENDRA KUMAR)	SR. DEE/TRD EASTERN RAILWAY/MALDA	(S. K. ANUJ)
SR. DEN/CORD EASTERN RAILWAY/MALDA	(JITENDRA KUMAR)	DEN/I EASTERN RAILWAY/MALDA	(BEENIT BHAGAT)
SR. D.O.M. EASTERN RAILWAY/MALDA	(RAJESH KUMAR)	DY.CEE/CON EASTERN RAILWAY/BGP	(B.K. BISWAS)
SR. DSTE EASTERN RAILWAY/MALDA	(S.P. YADAV)	DY. CSTE/CON EASTERN RAILWAY/MALDA	(B. KUSHWAHA)
SR. DCM EASTERN RAILWAY/MALDA	(PAWAN KUMAR)	DY.CE/CON EASTERN RAILWAY/MALDA	(G. L. MEENA)
SR. DEE/G EASTERN RAILWAY/MALDA	(M. K. VISHWAKARMA)	DEN/CON EASTERN RAILWAY/MALDA	(A. K. MANDAL)

ALL L.C GATE'S UPTO NEXT BLOCK STATION GANKAR:

SL. NO.	L-XING NO.	KM (FROM BDC)	CURRENT TVU
1.	20/C-CLASS/TRAFFIC	206.466	53169/JAN-2019 TO BE OPERATED TO 'SPL' CLASS
2.	21/C-CLASS/Engg.	209.683	6037/JAN-2019
3.	22/C-CLASS/Engg.	210.886	3657/JAN-2019

ALT-I

ALT-I(a):- DELETION OF L.C. GATE NO. 26 FROM JRLE STATION. AS PER SR. DOM/MLDT LETTER NO. T.WR1/SWR/05/22. MLDT DT. 19.05.2022.

ALT-I(b):- CORRECTION OF POINT CH-330.25M FROM 1 IN 8½ TO 1 IN 12 IN CONNECTION WITH RAISING OF SPEED FROM 15 KMPH TO 30 KMPH AS PER DY.CE/TRACK/II/HQ LETTER NO.W(7)G32/70 PT-5.KKK DT. 7.6.22. ACCORDINGLY FM POSITION AND CAL OF UP MAIN LINE HAVE BEEN CORRECTED. THIS WORK WILL BE EXECUTED BY OPEN LINE AND IT HAS BEEN SHOWN IN GREEN.

ALT-I(c):- SPECIAL NOTE ADDED FOR MINOR ALTERATION.

CSTE/CON E. RLY/KOLKATA — CE/CON/II E. RLY/KOLKATA

SR.DOM/ER/MLDT — SR.DSTE/ER/MLDT — SR.DCM/ER/MLDT — DY.CSTE/CON/ER/MLDT — DY.CE/CON/ER/MLDT — SR.DEN/CON/MLDT — JE/DRG/MLDT ALTERED BY

IRPSM PROJECT ID: 02.0315.12.1.30.001

PINK BOOK ITEM NO. 57 OF 2015-16

EASTERN RAILWAY
(CONSTRUCTION DEPARTMENT)

MALDA DIVISION

AZIMGANJ-FARAKKA SECTION [E-ROUTE]

ADDITION & ALTERATION OF YARD IN CONNECTION WITH PROPOSED DOUBLING BETWEEN MANIGRAM - NIMTITA.

जंगीपुर रोड स्टेशन

JANGIPUR ROAD STATION [E.S.P.] (JRLE)

PHASE-III & FINAL

SCALE :- 1CM = 10M (1:1000)

CE's DRG No. :- Y-198-2021

CAO/CON's DRG No. Y-391-2021 (ALT-I)

DY.CE/CON/MLDT's DRG No. Y-117-2021 (ALT-I)

Y-391-2021 E/18

18549